



GREGCO EXCAVATING, LLC

PO Box 129 - Lake Stevens, WA 98258-0129

Phone: 425 220 8289 Fax: 425 334 4642

colby.gregory@gregcoexcavating.com

November 16, 2023

RE: **RSCC Dam Repair Arlington, WA**

Subject: Bid Proposal and Scope Clarification's for Site work and Utilities

This proposal is based on performing all activities listed under "INCLUSIONS" with no obstructions or hindrances in any way that would otherwise slow down or modify the way in which the work is scheduled to be completed

INCLUSIONS:

EARTHWORK:		
Filter fence	450	LF
Deliver entrance rock	174	TCY
Place entrance rock *To be re used as 2' of ballast Rock	156	TCY
Strip topsoil-load (6")	7000	SF
Haul Topsoil onsite	162	TCY
Stockpile topsoil in neighborhoods field	162	TCY
Place sod in landscaping	162	TCY
Demo old concrete pipe	60	LF
Haul & dispose conc slabs	20	TCY
Mass excavation-load	220	TCY
Place access spoils on neighborhood field	400	TCY
Haul excavation onsite	1120	TCY
Excavate for cut off trench Max depth 12' max width 5'	1120	TCY
Place-compact treated onsite exc in cut off trench	1120	TCY
Process Bentonite treated native material @ 4%	1120	TCY
Mobilize/demobilize	10	HRS
General Conditions	23	HRS
STORM:		
PVC 6" finger drain	198	LF
Deliver 3/4"washed-infiltrator trench	40	TCY
Place infltr. trench exc onsite	41	TCY
Place unsuitable exc onsite	190	TCY
Deliver select backfill gravel borrow	190	TCY
Mobilize/demobilize	3	HRS
General Conditions	7	HRS

Excavate cut off trench per plans. 350' Long by up to 12' deep and 5' wide. Our proposal is based on little side wall sluffing.

Onsite soils to be used as backfill

Treat existing native material coming out of cut off trench excavation with a 4%+/- mixture of bentonite

Access to top of dam from both the North and South side

Proposal is based on one move-in/out

SPECIAL EXCLUSIONS:

- Screening of native materials
- Project related fees/costs for permits, permits, lab tests, inspections, and obtaining permits
- Survey layout and engineering, as-builts other than field drawn notes
- Coordination with Franchise Utilities
- CESL/Turbidity Monitoring
- Salvaging of any or all demolition materials
- Surcharges relating to material or fuel
- Providing of Water Meter, Water for Testing, Water for Dust Control, Paying for Water
- Over Excavation
- De-watering, Baker Tank, and Pumps associated with De-Watering
- Conditioning/additives/drying of soils
- Excavation, handling, and or disposal of materials deemed to be considered Hazmat or Contaminated
- Locating/hindrances of existing utilities not specifically identified on bid/contract drawings
- Removal of Boulders over 1 CY or excavation of Solid Rock
- Redistribution of topsoil, landscaping, hydro seeding, restoration or landscaping of any kind
- Removal and disposal of any existing tanks
- Bid is based off re-using native soils for Cut to Fill and Back-Fill except in R.O.W
- Sheet piling, Shoring, Tieback, Soldier Pile/Timber, Lagging
Shoring, removal of shoring elements
- Grades to be +/- one tenth
- All additional work outside of the inclusions are to be negotiated and agreed to in writing before “additional work” is to begin
- Sales WSST, tax, bonds
- Performance/installation/handling of any items not specifically listed under “*INCLUSIONS*”

BASE BID PROPOSAL VALUE **\$154,000.00**

ALTERNATES:

DEWATERING:		
Dewater set up & removal	1	LS
Dewatering *1 Month Rental	722	HRS
Mobilize/demobilize	2	HRS

Set up, 1 month rental and removal \$35,000.00.

Monthly rental for dewater \$25,000.00

***NOTE DEWATERING DOES NOT INCLUDE BAKER TANKS OR TURBIDITY MONITORING.
ASSUMING DISCHARGE LIKE EXISTING PUMPS**

This proposal is based upon, *Icicle Creek Engineers Civil plans Dated 7.20.20...*. Acceptance within 30 days in its entirety, schedule, and availability, review of approved contract drawings and subject to acceptable contract terms. This Proposal once accepted, must be included in the contract documents with this proposals Schedule of Values, Inclusions, and Exclusions, in its entirety unless negotiated otherwise. Please call 425-220-8289 or email at colby.gregory@gregcoexcavating.com should you have any questions or require additional information regarding this proposal.

Sincerely,
Colby Gregory
Estimator/ Project Manager
425.220.8289